SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAMBASIVA REDDY	
				Rate in Words	Rate in Figures
217	1.00	Supplying of multi function digital meter with three line back light LCD type display for voltage, Current, frequency, Power, power factor, KVA, KWH,KVAR suitable for 3 phase, 4 wire LT network with IP 54 degree of protection and completely wired as required with communication Port and Class 0.5s accuracy. ---- All terms and condition are as per Tender Document	Each	8000.00	Rupees Eight Thousand Only
218	3.00	Supplying and fixing of LED type panel board indicating lamp with required colour suitable for 220v A.C. 50 Hz 12/24v D.C. ---- All terms and condition are as per Tender Document	Each	442.00	Rupees Four Hundred Forty Two Only
219	2.00	Supplying ..... amps rated 3phase with neutral bus bar using required capacity electrolytic aluminum strips covered with heat shrinkable coloured PVC sleeve, mounted on phenolic/FRP/DMC insulator which are mounted on powder coated 40x6mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete. 100Amps 4x30x6mm Aluminum Strips ---- All terms and condition are as per Tender Document	Mtr	2135.00	Rupees Two Thousand One Hundred Thirty Five Only
220	8.00	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. and M.S. flat ... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint.40x40x6mm ---- All terms and condition are as per Tender Document	Mtr	263.00	Rupees Two Hundred Sixty Three Only
221	150000.00	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete. 14SWG ---- All terms and condition are as per Tender Document	sq.cms	0.37	Rupees And Paise Thirty Seven Only
222	4.00	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia ---- All terms and condition are as per Tender Document	No	2727.00	Rupees Two Thousand Seven Hundred Twenty Seven Only
223	4.00	Supplying fixing and wiring earth electrode for grounding of lifts, transformers, DG sets etc. using 40mm dia 2.9mm thick 2.5 mtr long GI pipe with GI funnel with mesh and suitable size reducer fixed on the top of the earth electrode. The funnel should be enclosed in a CC chamber of 400x400x400mm with a cast iron cover. The earth electrode shall have staggered holes of 12mm dia and the electrode should be covered 150mm all-round with alternate layers of salt and charcoal from the bottom of the CC chamber. The connection from the electrode is to be established through GI strip using GI bolts and nuts. ---- All terms and condition are as per Tender Document	No	4317.00	Rupees Four Thousand Three Hundred Seventeen Only
224	50.00	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required. GI strip 25x3mm ---- All terms and condition are as per Tender Document	Mtr	77.00	Rupees Seventy Seven Only
225	8.00	600x600x3mm GI Plate ---- All terms and condition are as per Tender Document	Each	784.00	Rupees Seven Hundred Eighty Four Only
226	50.00	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required. 25x3mm Copper strip 25x3mm ---- All terms and condition are as per Tender Document	Mtr	523.00	Rupees Five Hundred Twenty Three Only

Contractor

Executive Engineer,
Project Division,Yelahanka

SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAM REDDY	
				Rate in Words	Rate in Figu
227	30.00	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A. 4 core 10 sqmm ---- All terms and condition are as per Tender Document	Mtr	118.00	Rupees One Hundred Eighteen Only
228	25.00	4 core 16 sqmm ---- All terms and condition are as per Tender Document	Mtr	140.00	Rupees One Hundred Forty Only
229	150.00	3.5 core 95 sqmm ---- All terms and condition are as per Tender Document	Mtr	445.00	Rupees Four Hundred Forty Five Only
230	55.00	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.On wall /Structure 6 sqmm to 16 sqmm ---- All terms and condition are as per Tender Document	Mtr	31.00	Rupees Thirty One Only
231	250.00	25 sqmm to 75 sqmm ---- All terms and condition are as per Tender Document	Mtr	34.00	Rupees Thirty Four Only
232	65.00	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete. In soil (ordinary) --- All terms and condition are as per Tender Document	Mtr	78.00	Rupees Seventy Eight Only
233	10.00	Asphalt cutting ---- All terms and condition are as per Tender Document	Mtr	117.00	Rupees One Hundred Seventeen Only
234	65.00	Providing and filling sand in excavated trench to cover already laid UG cable to a depth of 150mm all-round the cable. ---- All terms and condition are as per Tender Document	Mtr	103.00	Rupees One Hundred Three Only
235	2.00	Supplying and fixing of heavy duty cable glands suitable for UG cable of 1.1 KV class (metal only) 25mm dia ---- All terms and condition are as per Tender Document	Each	86.00	Rupees Eighty Six Only
236	2.00	32mm dia ---- All terms and condition are as per Tender Document	Each	122.00	Rupees One Hundred Twenty Two Only
237	10.00	Supplying and fixing 2mm thick perforated cable tray with powder coated paint on existing MS angle support using necessary GI bolts/nuts and washer or welding as required.300x50mm ---- All terms and condition are as per Tender Document	Mtr	547.00	Rupees Five Hundred Forty Seven Only
238	100.00	Supply and laying double walled corrugated (DWC) HDPE Pipe including all necessary connecting Sockets/Couplings/Tees/Bends/End-caps of same materials in existing trench as per IS 14930 part -II suitable for drawing underground cables. 40mm OD / 32mm ID ---- All terms and condition are as per Tender Document	Mtr	98.00	Rupees Ninety Eight Only
239	75.00	50mm OD / 38mm ID ---- All terms and condition are as per Tender Document	Mtr	151.00	Rupees One Hundred Fifty One Only
240	100.00	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes. 1.5 sqmm ---- All terms and condition are as per Tender Document	Each	2.00	Rupees Two Only
241	80.00	2.5 sqmm ---- All terms and condition are as per Tender Document	Each	3.00	Rupees Three Only
242	24.00	4 sqmm ---- All terms and condition are as per Tender Document	Each	6.00	Rupees Six Only
243	12.00	6 sqmm ---- All terms and condition are as per Tender Document	Each	6.00	Rupees Six Only
244	32.00	10 sqmm ---- All terms and condition are as per Tender Document	Each	6.00	Rupees Six Only
245	8.00	16 sqmm ---- All terms and condition are as per Tender Document	Each	11.00	Rupees Eleven Only
246	8.00	35 sqmm Long Barrel ---- All terms and condition are as per Tender Document	Each	35.00	Rupees Thirty Five Only
247	200.00	Supplying and running GI/Copper conductor for grounding and (along with other wires in conduit system of wiring) using necessary suitable size clamps, nails, guttas/spacers etc. GI Wire 8 SWG ---- All terms and condition are as per Tender Document	Mtr	19.00	Rupees Nineteen Only
248	4.00	Supplying of 1440rpm heavy duty exhaust fan with bracket blades suitable to operate on 230V 50Hz, AC Supply complete.15" Sweep (450mm) ---- All terms and condition are as per Tender Document	Each	4500.00	Rupees Four Thousand Five Hundred Only

Contractor

Executive Engineer,
Project Division,Yelahanka

SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAMBASIVA REDDY	
				Rate in Words	Rate in Figures
249	23.00	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system. 48" Sweep (1200mm) REGULAR model ---- All terms and condition are as per Tender Document	Each	2350.00	Rupees Two Thousand Three Hundred Fifty Only
250	100.00	Supplying and drawing PVC flexible one pair telephone unarmoured tinned copper cable. 2Pair ---- All terms and condition are as per Tender Document	Rmt.	13.00	Rupees Thirteen Only
251	1.00	Supplying, erecting, testing & commissioning of OFF-LINE UPS system suitable for operation on 230V, 50Hz, A/C supply, with all accessories complete and Excluding batteries and wiring complete. 5 KVA OFF LINE UPS Two Hour back up Excluding 6x 150Ah batteries ---- All terms and condition are as per Tender Document	Each	50000.00	Rupees Fifty Thousand Only
252	6.00	Supplying, installation, testing & commissioning of 12Volts ..AH batteries in poly propylene container for D.G. sets. Low maintenance batteries, plate type.150AH capacity. Acid batteries ---- All terms and condition are as per Tender Document	Each	20000.00	Rupees Twenty Thousand Only
253	1.00	Supplying, erection, testing and commissioning of .....KVA Diesel Generating Set on existing CC platform Comprising of Diesel Engine Developing ..... BHP @ 1500 RPM confirming to BS 5514.The engine should be turbocharged, Air/water cooled with 10 % over load for 1hour in every 12 hours of operation coupled to suitable capacity alternator rated at 415V, 0.8 PF(lag) 50 Hz, 3 phase, 4 wire system, confirming to BS 5000/IS 4722. The alternator shall be of brushless type ,Screen protected, revolving field, Mounted on suitable Channel Iron Base Frame, Complete with suitable capacity Fuel Tank, required nos. of Batteries of 12/24V as per requirement, Acoustic enclosure as per CPCB Approved Norms. 62.5kva/50kw ---- All terms and condition are as per Tender Document	Each	570000.00	Rupees Five Lakh(s) Seventy Thousand Only
254	1.00	Supply, Erection, testing and commissioning of AMF panel suitable for .....KVA DG set. The panel is of cubical type base/floor mounting control panel with hinged doors, undrilled bottom gland plate, aluminum Bus Bar with the accommodation for .....amps 4 pole contactor for alternator with thermal O/L relay,..... Amps 4 pole contactor for mains, HRC fuse for short circuit protection, Microprocessor based AMF module with supply failure timer, Restoration timer, 3 impulse automatic engine start/stop logic, Mains/generator voltage, ...capacity bypass switch and frequency sensing, PCC 1301 controller with water temperature/Lube oil pressure/ engine speed, Voltage/ampere/Frequency/ KVA, Running-hour count, No of starts, Fault indication, over /under speed, Fails to start, Low oil pleasure, High engine temperature, Under/over voltage, over current, Earth fault relay, with indications for Mains on, Load on Mains, Battery charger on Push buttons AMf module by pass Mode, Battery charger unit with inbuilt Auto/Manual and Flat/Boost facility. Up to 62.5kva ---- All terms and condition are as per Tender Document	Each	92400.00	Rupees Ninety Two Thousand Four Hundred Only
255	1.00	Supply , installation, testing and commissioning of Table top model chairman unit with gooseneck mic with ring LED and interconnection cable and out sockets for linking next unit with talk and priority switch aluminum/PVC housing and headphone sock ---- All terms and condition are as per Tender Document	No	12400.00	Rupees Twelve Thousand Four Hundred Only
256	2.00	Supply, installation, testing and commissioning of, 9 core multistrand high gain low loss cable with required end connectors 10meter to connect between the delegate unit and controller including charges for labour, lead and lifts, loading and unloading ---- All terms and condition are as per Tender Document	No	220.00	Rupees Two Hundred Twenty Only
257	5.00	Supply, installation, testing and commissioning of compact ceiling speaker with Back Can power handling up to 6 watt RMS/ watt /100volt@ 1456 ohms single channel. selectable taping 5" LF driver and tweeter ---- All terms and condition are as per Tender Document	No	1450.00	Rupees One Thousand Four Hundred Fifty Only

Contractor

Executive Engineer,
Project Division,Yelahanka

SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAN REDDY	
				Rate in Words	Rate in Figu
258	4.00	Supply, installation, testing and commissioning of compact Wall mount speaker with power handling up to 40Watt RMS 0/100volt@ 1456 ohms single channel. selectable taping Specs: Power handling : 15 to 30 watt Frequency response : 80 Hz t0 18khz Spl: ---- All terms and condition are as per Tender Document	No	6890.00	Rupees Six Thousa Eight Hundred Ninety Only
259	1.00	Supply, installation, testing and commissioning of booster amplifier with power handling of 250 to 300 watt RMS 4ohms Dual and 100/70 volt output on bridge mode single channel Rack mountable Specs: frequency response : 20 htz to 20khtz ---- All terms and condition are as per Tender Document	No	27550.00	Rupees Twenty Seven Thousand Five Hundred Fifty Only
260	1.00	Supply, installation, testing and commissioning of 12Channel 12mic/line 2-4 Stereo input mixer with built in 3 to 4 band semi parametric eq 2 bus or 4 bus and 2 to 4 aux outs 2 stereo return. Specs: frequency response of 20 htz to 20 kHz with THD o ---- All terms and condition are as per Tender Document	No	22000.00	Rupees Twenty Two Thousand Only
261	1.00	System Racks Supply, installation, testing and commissioning of 19" 20/15U 580 Depth system rack with Front glass door , back door with heavy duty wheels with cable manager and power strip and termination plates for signal and speaker out system. ---- All terms and condition are as per Tender Document	No	12800.00	Rupees Twelve Thousand Eight Hundred Only
262	750.00	Speaker Cables Supply, installation, testing and commissioning professional grade 2.5 sq mm TIN coated low loss 2 core multi strand Oxidation Free speaker cable including, lead and lifts, loading and unloading, cost of conveyance for all the materials with the accessories. --- All terms and condition are as per Tender Document	meter	38.00	Rupees Thirty Eight Only
263	1.00	Connectors and I/C Cables Supply, installation, testing and commissioning of professional grade audio connectors for inter connection cables with in the rack and other units as well auditorium as required including charges for labour, lead and lifts, loading and unloading, cost of conveyance for all the materials with the accessories required for completion as per the detailed specifications. Neutrick/SR/Amphenol/nT/MX/Equivalent. ---- All terms and condition are as per Tender Document	Set	240.00	Rupees Two Hundred Forty Only
264	386.00	Fixing all types and all capacities of fluorescent / false ceiling / spot light / CFL / LED fittings indoor on the wall / ceiling / rafters / girders using 23/0.0076" twin twisted PVC insulated wires, required Nos of round blocks and clamps.On wall / ceiling / Rafter / Girders ---- All terms and condition are as per Tender Document	Each	98.00	Rupees Ninety Eight Only
265	23.00	Fixing a ceiling / wall mounting fan of all capacities and all types, with necessary clamps and 'S' hook made out of 15mm dia MS rod, with 5 amps. ceiling rose of approved quality with necessary length of 23 / 0.0076 inch PVC insulated twin twisted wire of approved quality, mounted on a suitable size wooden board and wired. ---- All terms and condition are as per Tender Document	Each	237.00	Rupees Two Hundred Thirty Seven Only
266	4.00	Fixing one exhaust fan in the nitch already left in the wall with bolts and nuts and 5 amps. ceiling rose with sufficient length of 23 / 0.0076 inch PVC insulated twin core wire. ---- All terms and condition are as per Tender Document	Each	412.00	Rupees Four Hundred Twelve Only

Contractor

Executive Engineer,
Project Division,Yelahanka

SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAMBASIVA REDDY	
				Rate in Words	Rate in Figures
267	1.00	Constructing brick masonry circular type manhole 1.67 m internal dia at bottom 1.67m deep and 0.56m dial at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and downsize granite metal and making necessary channel in cement concrete M 15 with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560 mm internal diameter confirming IS:12592, total weight cover and frame to be not less than 182 kg, fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of machineries complete as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be seperately). ---- All terms and condition are as per Tender Document	Nos	22815.00	Rupees Twenty Two Thousand Eight Hundred Fifteen Only
268	10.00	Providing cast iron footrest and fixing in manhole with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, HOM of machineries complete as per specifications. specification no. KBS ---- All terms and condition are as per Tender Document	Nos	248.00	Rupees Two Hundred Forty Eight Only
269	10.00	Making connection of drain or sewer line of size 160 to 200mm external dia with existing manhole including breaking into and making good the walls, floors with cement concrete M 15 with 20mm and down size granite metal, cement plastered on both sides of mix 1:3, finished with a floating coat of neat cement and making necessary channels for the drain, including cost of materials, labour charges, HOM of machineries complete as per specifications. ---- All terms and condition are as per Tender Document	M	2458.00	Rupees Two Thousand Four Hundred Fifty Eight Only
270	4.00	Constructing brick masonry inspection chamber 600x600mm and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non- modular bricks of class designation 50 in cement mortar 1:5, C.I cover with frame (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38kg (weight of cover 23kg and weight of frame 15kg) R.C.C top slab with cement concrete M 15 with 20mm and down size granite metal, foundation concrete M5 with 40mm and down size granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, HOM of machineries complete as per specifications. ---- All terms and condition are as per Tender Document	Nos	9670.00	Rupees Nine Thousand Six Hundred Seventy Only
271	75.00	Providing and fixing unplasticised PVC pipes 10.00 kg/sq.cm working pressure chemp plast/wavin or equivalent make with pipe fittings, clips, making good the floor , including cost of all materials, labour charges, HOM of equipment and testing complete as per specifications. do- with 90mm outer dia ---- All terms and condition are as per Tender Document	m	519.00	Rupees Five Hundred Nineteen Only
272	65.00	do- with 110mm outer dia ---- All terms and condition are as per Tender Document	m	743.00	Rupees Seven Hundred Forty Three Only
273	50.00	do- with 160mm outer dia ---- All terms and condition are as per Tender Document	m	1566.00	Rupees One Thousand Five Hundred Sixty Six
274	20.00	Providing and fixing white vitreous china clay, water closet europeon type (pedestal type, p-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level,P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets , 40mm diameter flush pipe fittings and clamps, overflow arrangements with specials and 25mm mosquito proof coupling of approved design,painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour complete as per specifications. ---- All terms and condition are as per Tender Document	Each	5540.00	Rupees Five Thousand Five Hundred Forty Only

Contractor

Executive Engineer,
Project Division,Yelahanka